6. The name of the successful competitor, whose tender has been accepted, will be posted on the notice board in the Executive Engineer's office in due course. No enquiries regarding the acceptance or rejection of a tender will receive any reply.

7. On acceptance of one of the tenders, the earnest money on rejected tenders will be returned.

Description of work.	*Unit of work*	*Rate per unit.*
Cast iron pipes 2″	438 feet.	
Galvanized pipes 2″	400 ,,	
Do 1¼″	535 ,,	
Do 1″	10,000 ,,	
Gland cock 1″	No. 55	
Galvanized bend 1″	No. 60	
Do elbows	No. 360	
Reducing colars 1″×¾″	No. 188	
Cast iron tie 3″×2″.	No. 2	
Spare collars 1″	No. 188	

These pipes and fittings should be delivered at the store-yard of the Executive Engineer's office.

SPECIFICATION.

The pipes to be of uniform bore and thickness throughout, free from all flaws, well coated and of water quality.

V. RANGASAMY IYENGAR,
Ex. Engr., Water-Supply & Stores Dn., Bangalore.

HASSAN DIVISION.

Invites the attention of the public to the Notification in the *Mysore Gazette*, No. 2, dated 12th January 1905, calling for tenders for restoring Santesivara tank.. Registered No. 147, Channarayapatna Taluk.

Invites the attention of the public to the Notification in the *Mysore Gazette* No. 2, dated 12th January 1905, calling for tenders for restoring Metikere tank, Registered No. 12-143, Channarayapatna Taluk.

Invites attention of the public to the Notification in the *Mysore Gazette*, No. 2, dated 12th January 1905, calling for tenders for restoring Nowle tank, Registered No. 179 in Channarayapatna Taluk.

Notification dated 6th January 1905.

The road from Sukravarsante in Manjarabad Taluk to Subrahmania being under improvement, night traffic between the 18th and 26th miles of it is considered unsafe, until further notice.

Dated 10th January 1905.

1. Notice is hereby given that sealed tenders will be received at the office of the Executive Engineer, Hassan Division, up to 31st January 1905, for restoring Chelya-Hirikere tank, Registered No. 225, Channarayapatna Taluk. An approximate estimate of quantities is given below. These quantities are not guaranteed. The work should be completed by the end of March 1907.

2. The plans, detailed estimate and conditions may be seen at the Executive Engineer's office at Hassan between the hours of 11 A.M. and 5 P.M.

3. Tenders should be submitted on printed forms which may be obtained from the Executive Engineer. The tenders should be accompanied by a statement in the form given below, showing the rates at which the different items specified will be executed.

4. Each tender must be accompanied by a deposit of rupees two hundred in cash or Government Promissory Notes, as earnest money, and be superscribed "Tender for restoring Chelya-Hirikere tank, Registered No. 225, Channarayapatna Taluk," in default of which, tenders will be rejected.

5. The final acceptance of any tender will rest with the Superintending Engineer, who does not bind himself to accept the lowest or any tender or to assign any reason whatever for the rejection of any tender.

6. Within eight days of the acceptance of the tender, the successful competitor will be required to execute the usual contract bond; in default of which, his tender will be considered cancelled, and his earnest money will be forfeited.

7. The name of the successful competitor, whose tender has been accepted, will be posted on the notice board in the Executive Engineer's office in due course. No enquiries regarding the acceptance or rejection of a tender will receive any reply.

8. On acceptance of one of the tenders, the earnest money on rejected tenders will be returned.

Restoring Chelya-Hirikere tank, Registered No. 225, Channarayapatna Taluk.

Items of work.	*Per.*	*Quantity.*
Bund—		
Earthwork	C. yds.	18,413
Forming bund including revetment and turfing	Lump sum	Rs.
Clearing silt	C. yds.	905
Turfing	S. yds.	13,356
Old stone work	C. yds.	630
New stone work	"	4,319
Gravel backing	"	3,211
Grade stones	No.	36
Index stones	"	36
Date and registered number stones	"	2
Gauge stone	"	1
B. M. stones	"	2
Clearing bushes and trees	Lump sum	Rs.
Sluices—		
Blocking up the old sluices	Lump sum	Rs.
Constructing 2 new sluices as per type design	No.	2
Waste weir—		
Cutting rock	C. yds.	25
Earthwork excavation	"	345
Rough stone in mortar	C. ft.	6,753
Burnt stone slabs	S. ft.	1,424
Concrete	C. ft.	1,976
Pointing	Sqr.	38·24
Rough stone work	C. yds.	168
Clearing site	Lump sum	Rs.

C. A. MAHADEVA SASTRI, *Executive Engineer.*

SHIMOGA DIVISION.

Dated 16th January 1905.

1. Notice is hereby given that sealed tenders will be received at the office of the Executive Engineer, Shimoga Division, up to 13th February 1905, for restoring Gogga-Honnallikere, Registered No. 267, Shikarpur Taluk. An approximate estimate of quantities is given below. These quantities are not guaranteed. The work should be completed by the end of February 1906.

2. The plans, detailed estimate and conditions may be seen at the Executive Engineer's office at Shimoga between the hours of 11 A.M. to 5 P.M.

3. Tenders should be submitted on printed forms, which may be obtained from the Executive Engineer. The tenders should be accompanied by a statement in the form given below, showing the rates at which the different items specified will be executed.

4. Each tender must be accompanied by a deposit of rupees two hundred in cash or Government Promissory Notes, as earnest money, and be superscribed "Tender for restoring Gogga-Honnallikere," in default of which, tenders will be rejected.

5. The first acceptance of any tender will rest with the Superintending Engineer, Western Circle, who does not bind himself to accept the lowest or any tender or to assign any reason whatever for the rejection of any tender.

6. Within eight days of the acceptance of the tender, the successful competitor will be required to execute the usual contract bond; in default of which, his tender will be considered cancelled, and his earnest money will be forfeited.

7. The name of the successful competitor, whose tender has been accepted, will be posted on the notice board in the Executive Engineer's office in due course. No enquiries regarding the acceptance or rejection of a tender will receive any reply.